



राष्ट्रीय गतिशील दिव्यांगजन संस्थान

National Institute for Locomotor Disabilities (Divyangjan)

(दिव्यांगजन सशक्तिकरण विभाग, सामाजिक न्याय एवं अधिकारिता मंत्रालय, भारत सरकार)

Department of Empowerment of PwDs (Divyangjan), Ministry of Social Justice and Empowerment, Govt. of India

B.T. ROAD, BON-HOOGHLY, KOLKATA-700090

बी.टी .रोड बनहुगली,कोलकाता-700090

Phone: 2531-0279, 2531-0610/Tele Fax: 2531-8379/E-mail: mail@nioh.in and web: www.niohkol.nic.in

No –Rect/2nd floor/CE/29/2004/NIOH/Part I/79(7)

Dated– 05/04/2017

Notice Inviting Tender

Sealed Tenders are invited by the Director, NIOH, B.T.Road, Kolkata-90 in the institute's prescribed form from the reputed, bonafide and resourceful agencies who are carrying out the similar type of works in PWD/CPWD or any other Government organization to undertake the work as detailed below:

1. Name of work : Providing False ceiling and necessary repairing and distempering work in Computer lab at the 2nd floor of Institute's main building.
2. Estimated Amount put to tender : Rs. 1,36,362.19
3. Time of Completion : 21 (Twenty One) days
4. Earnest Money : Rs.3,410.00 to be submitted shall be in the form of Bank Draft/Pay order in favour of NATIONAL INSTITUTE FOR THE ORTHOPAEDICALLY HANDICAPPED payable at Kolkata, 90.
5. Performance Gurrantee : 5% of tender amount in form of demand draft in favour of NATIONAL INSTITUTE FOR THE ORTHOPAEDICALLY HANDICAPPED payable at Kolkata, 90 within a period of 7 (Seven) days from the date of letter of acceptance. The same will be returned after Satisfactorily completion of work.
6. Cost of Tender Paper : Rs. 500.00 payable in cash for each set of tender paper.
7. Last Date of Receiving Application for issue of Tender Paper : **10-04-2017** up to 4.00 PM
8. Last Date of issue of Tender Paper : **11-04-2017** up to 4.00 PM
9. Last Date of Receiving filled in Tender Paper : **13-04-2017** up to 3.00 PM
10. Date of opening of Tender : **13-04-2017** at 3.30 PM

11. Tender document can also be downloaded from the web site (www.niohkol.nic.in). In that case the DD/Pay order towards the cost of tender paper of Rs 500.00 to be deposited on or before last date of issue of tender paper and is to be submitted with completed tender document in a separate envelop.

I/C CE DEPARTMENT

NILD , KOLKATA

General Instruction and terms & conditions

Kindly submit following document along with tender for the above works -

1. Attested copy of satisfactory completion certificate from an officer not below the rank of Executive Engineer of similar nature of work as given below :
 - i) One similar work of value not less than 1.09 lakh in any government/semi government or autonomous body during last seven years ending 31st March,2017.
 - ii) Two similar works each of value not less than 0.82 lakh in any government/semi-government or autonomous body during last seven years ending 31st March, 2017.
 - iii) Three similar works each of value not less than 0.55 lakh in any government/semi-government or autonomous body during last seven years ending 31st March,2017.
2. Copy of Registration certificate of Trade License, VAT, PAN Card, Partnership deed in case of Partnership firm.
3. Demand Draft/Pay Order as Earnest money of the amount as indicated in NIT.
4. Price schedule with rate offered.

Sealed envelopes containing above documents are to be enclose in an envelope, and dropped in the tender box of Engineering Section within **13.04.2017** between 10AM to 3PM addressed to the Director, NIOH, B.T. Road, Bonhooghly, Kolkata-90 with the name of work **“Providing False ceiling and necessary repairing and distemperring work in Computer lab at the 2nd floor of Institute’s main building.”**boldly superscripted on the top of the mother envelop.

Submission and opening of tender.

- A) Telegraphic/cabled/faxed/e-mail or any type of exposed tender will be summarily rejected.
- B) Sealed tender will be opened in presence of tenderer/representative at Date & time specified in the NIT.

Earnest money and security deposit

All tender must be accompanied with earnest money deposit as indicated above. Tenders without EMD will be rejected. The EMD will be returned to the unsuccessful tenderers & shall be adjusted with Security deposit in case of successful tenders. No interest will be paid in EMD or Security deposit.

The security deposit @10% of tender amount will be recovered from the contractor’s bill. The same will be released after 6 (Six) months from the date of completion or after passing of final bill whichever is later.

I/C CE DEPARTMENT
NILD , KOLKATA

ADDITIONAL TERMS AND CONDITIONS

1. Work should be carried out as per CPWD specification 2009 Volume 1 & 2 with upto date correction slips.
2. The works is to be executed in such a manner that day to day activities of the institute may not hamper.
3. Work may be require to execute on emergency basis i.e. on Sundays/holidays/beyond office hours depending upon the situation without any extra claim/ charge.
4. Shifting of furniture, machinery etc. before and after execution of work shall be a part of tender work.
5. Shifted materials may be kept under the custody of contractor till those are handed over to the in charge of respective unit for whom work executed.
6. Any damage occurs during shifting of Government article should be make good by the contractor.
7. Building rubbish/ malba/ similar unserviceable dismantled or waste materials are to be disposed outside the NILD campus and no extra payment will be made in this regard.
8. Useful materials available by dismantling are to be stacked in a place within the NILD campus as per direction of the Engineer-in-charge.
9. **(a)** The contractor shall have to make own arrangement of water and electricity for which nothing extra will be paid on that account subject to the condition that the water used shall be fit for construction purpose.
(b) Water and electricity if possible may be supplied to the contractor on request. Water charges @ 1% of gross amount of bill and electricity charges at prevailing CESC rate as per actual consumption will be recover from the bill. But in case of any disruption of supply the contractor shall make his own alternative arrangement. No claim of damage or refund of water and electrical charge will be entertained on account of such occasion.
(c) Construction cess @ 1% of gross amount of bill will be recovered from the bill.
9. The work is to be completed within the stipulated period. In case of delay a penalty @ ½ percent per week subject to the maximum of 10% of the tender amount will be Recovered from final bill.

NOTE

If any document furnish during submitting the tender paper are found false, incorrect or misleading even after opening of tender, the tender may be declare cancel.

The court of Kolkata will only be the jurisdiction to deal with and decide on any dispute whatsoever arising out of this tender.

The Authority of the Institute reserve the right to reject any of all tender paper without assigning any reason thereof.

I/C CE DEPARTMENT
NILD , KOLKATA

Copy to

1. Web Site , NIOH
2. Account Officer , NIOH
3. DAK File , NIOH
4. Notice Board , NIOH
5. The Director , MSME – DI
111 & 112, B.T. Road, Kolkata – 700 108 with a request to display on office notice board.
6. The Director , Indian Statistical Institute
203, B.T. Road, Kolkata – 700 108 with a request to display on office notice board.
7. The Chief Engineer (EZ III) CPWD. Nizam Palace.
234/4, AcharayyaJ.C.Bose Road, Kolkata – 700020 with a request to display on office notice board.

I/C CE DEPARTMENT
NILD , KOLKATA

NATIONAL INSTITUTE FOR THE LOCOMOTOR DISABILITIES (DIVYANGJAN)
(Department of Empowerment of PwDs, Under Ministry of Social Justice & Empowerment, Government of India)
B.T. Road, Bon-Hooghly, Kolkata-700090

PRICE SCHEDULE

Based on CPWD Delhi Schedule of Rate 2014 enhance by current cost Index @16.19%

Name of Work :-	<u>Providing Flase ceiling and necessary repairing and distempering work in Computer lab at the 2nd floor of Institute's main building.</u>
------------------------	--

SL NO.	Description of Work	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. 12.5 mm thick fully Perforated Gypsum Board tile made from plasterboard having glass fibre conforming to IS: 2095 part I, of size 595x595 mm, having perforation of 9.7x9.7 mm at 19.4 mm c/c with center borders of 48 mm and the side borders of 30 mm, backed with non woven tissue on the back side, having an NRC (Noise Reduction Coefficient) of 0.79, with 50 mm resin bonded glass wool backing.	80.00	Sqm	1,342.23	107,378.15

2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.30	Cum	7,494.26	2,248.28
3	Cleaning concrete surface by removing dirt and debris, marking defective locations and removing loose concrete by careful stripping until hard surface is exposed, cutting the concrete to regular shape, wire brushing the exposed surface and removing debris from the site complete as per direction of Engineer-in-charge.	10.00	Sqm	96.00	960.00
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement : 4 fine sand)	12.00	Sqm	287.92	3,455.03
5	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	12.00	Sqm	189.80	2,277.56
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	22.00	Sqm	86.45	1,901.80
7	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	126.00	Sqm	11.50	1,449.35
8	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water tinnable priming coat with cement primer	126.00	Sqm	104.22	13,132.03
9	Applying epoxy based reactive jointing agent for joining old concrete with fresh concrete to be applied within manufacturer's specified time as per manufacturer's specification. (0.4 Kg / sqm of concrete surface)	10.00	Sqm	356.00	3,560.00
Total :					136,362.19

I/C CE Dept.

I/We agree to carry out the above work AT PAR/

Below/Above the rates shown in the Price Schedule.

Contractor's Signature :